APEX 3224 MOBILE STAGE



mobilestages.miami / apex.miami

786-504-2369 786-255-4949

Apex 3224

Mobile Hydraulic Stage

Rental/Sales/Service 786-504-2369 / 786-255-4949 apex.miami / mobilestages.miami





The APEX 3224 features a 32′ wide x 24′ deep x 17′ tall stage area, with the capability of additional flooring, utilizing our connectable deck extensions. This stage comes standard with a swing-down gooseneck trailer hitch and/or king- pin style hitch, 2000# capacity speaker wing extensions, steel wheels, hydraulic out-riggers, all aluminum floors, all aluminum trailer frame construction, two dual axles, and a gas powered motor. Aluminum wheels, aluminum stairs, aluminum handrails, 70% blow-through back drops, 4′ x 8′ deck extensions, out-rigger pads, a wind deflector, an electric back-up motor.

Specifications:

Trailer:

Trailer Length- 34', Trailer Width 102" Trailer Height 12'2" Trailer Weight 14,150# Tongue Weight 1,800# Axle Rating 2x10,000#

Stage Deck:

Floor Size 32' by 23'8" Floor Height 46"-66" Ground to Roof 23'1" Structure Floor Support Marine ply/Alum 16 - 8,000# jacks

Stage Roof:

Covered Roof 26'3" x 34' Deck to Roof Top 16'6"

Deck to Front-stage 17' I-beam Deck to Center 16'6" I-beam Deck to Back-stage I-beam 16'

Surface Fiberglass/Alum

Beam Loads:

Fly Bays 4@2,000each
Front-stage I-beam 1,000# evenly dist.
Center I-beams 2@750# evenly dist.
Back-stage I-beam 1,000# evenly dist.
PTR Cantilever 1,000 evenly dist.
Total Roof Capacity 14,500#
Fly Bay Bar Length 2'3"

Other:

Install Time 30min-1 hour with 2 guys Hauling Mode- Gooseneck hitch

Power Source Secondary Power 5hp Honda Motor 1.5hp electric 110

REFLECTIONS PRODUCTIONS INC.

APEX XXXII SHOWMOBILE 3224 Contact: Thomas G. Mitchell 786-255-4949

















APEX 3224 SPECIFICATIONS

<u>Trailer:</u> <u>Other:</u>

Length 34' Personnel
Width 102" Required Site Prep None

Height 12'2" Hauling Mode Pick-Up Truck
Cargo Space 6'11" x 31'4" Power Source 5 hp Honda Motor

Cargo Capacity 4050# Secondary Power 1.5 hp electric 110 Motor

2

Trailer Weight 14150#
Tongue Weight 1800#

Tires:

Rear Axle Rating 9100# Tire Size 235/85/R16
Front Axle Rating 9100# Rims 16x6

GVWR 20000# Cold Tire Infl. 109 PSI

Stage Deck:

Floor Size 32' x 23'8"
Floor Height 46" to 66"
Ground to Roof 22'7"
Floor Rating 85" sq/ft
Plywood Rating 150# sq/ft

Structure Marine Plywood/Alum

Floor Support 16-7000# Jacks

Stage Roof:

Covered Roof 26'3" x 34'
Deck to Roof Top 16'7"

Deck to Bottom of Ctr I-Beam

Deck to Bottom of Downstage I-Beam 15'7"

Deck to Bottom of Upstage I-Beam 15'1"

15'4"

Surface Fiberglass/Alum

Roof Lifting Capacity 4500# Fly Bays 1000# ea.

Downstage I-Beam 1000# evenly distr.
Upstage I-Beam 1000# evenly distr.
Center I-Beam 1000# evenly distr.

Total Roof Capacity 8000# Slide Out Bar Length 2'3"





3/7/2023

Progressive Products & Apex Stages 3305 Airport Circle Pittsburg, KS 66762 Attn: Todd Allison

RE: Apex 3224 Mobile Stage CRE Project No: 23.534.01

Dear Todd:

Clark Reder Engineering Inc. has completed our review of the Apex Stages 3224 Mobile Stage for conformance to the 2018 IBC as well as the 2021 IBC for general use in the United States. Our scope was to review the engineering calculations previously developed by Clark Reder Engineering in accordance with earlier versions of the International Building Code, ASCE 7, and the Aluminum Design Manual.

Our review confirms that the mobile stage structure requires no changes to the High Wind Action Plan or Allowable Loading criteria, which are included with this package. CRE has determined that the 3224 Apex Mobile Stage Unit represents a safe design in accordance with the structural provisions of the 2018 and 2021 International Building Code and is fit for use in all 50 states. Our assumption is based on the following:

- The unit is built and used in accordance with the manufacturer's guidelines.
- The unit is routinely inspected, and an inspection log is kept current.
- The unit is not damaged and is in good condition.

This stamped document is valid for use through the expiration of the Engineering stamps located on the subsequent pages or when the building code changes to a more current edition of the International Building Code than listed above.

We trust this information is suitable for your needs at this time. Please do not hesitate to contact our office with any questions or comments.

Regards,





Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com

Alabama



Daniel J. Clark, P.E. P.E. #: 31076

Alaska



Daniel J. Clark, S.E. P.E. # SE14360

Arizona



Jeffrey M. Reder, P.E. P.E. # 50654

Arkansas



Daniel J. Clark, P.E. P.E. # 14355

California



Daniel J. Clark, S.E. P.E. # S5317

Colorado



Jeffrey M. Reder, P.E. P.E. # PE0051394

Connecticut



Daniel J. Clark, P.E. P.E. # 27576

Delaware



Jeffrey M. Reder, P.E. P.E. # 17438

District of Columbia



Jeffrey M. Reder, P.E. P.E. # S920119

CRE Project #: 23.534.01



Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com

Florida Hawaii Georgia No. 14362-S 03/07/20 Jeffrey M. Reder, P.E. Jeffrey M. Reder, P.E. Jeffrey M. Reder, P.E. P.E. # 68622 P.E. # PE034581 P.E. # 14362-S Idaho Illinois Indiana Inc. is a professional design firm registered in Illinois #184.006693 Clark Reder Engineering, STATE OF WOIANA WALLEY Jeffrey M. Reder, S.E. Daniel J. Clark, P.E. Jeffrey M. Reder, P.E. P.E. # 14947 P.E. # 81006866 P.E. # PE11600603 Iowa **Kansas** Kentucky Jeffrey M. Reder, P.E. Daniel J. Clark, P.E. Jeffrey M. Reder, P.E. P.E. # 19998 P.E. # 21809 P.E. # 23597

CRE Project #: 23.534.01 Date: 03/07/2023 Engineer: JMR

Project: Apex 3224



Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com

Louisiana



Jeffrey M. Reder, P.E. P.E. # 30304

Maine



Daniel J. Clark, P.E. P.E. # 12873

Maryland



Professional Certification: I hereby certify that these documents were prepared or approved by me, and that I am a duly licensed professional engineer under the laws of the State of Maryland. Expiration Date: 01/29/2024

Jeffrey M. Reder, P.E.

P.E. # 38421

Massachusetts



Jeffrey M. Reder, P.E. P.E. # 48535

Michigan



Jeffrey M. Reder, P.E. P.E. # 6201056952

Minnesota



hereby certify that this plan, specification, o report was prepared by me or under my direct supervision and that I am a duly licensed Professional Engineer under the laws of the State of Minnesota.

Typed or Printed Name: JEFFREY M. REDER
Date: 03/07/2023 License #: 56104

Jeffrey M. Reder, P.E. P.E. # 56104

Mississippi



Daniel J. Clark, P.E. P.E. # 20589

Missouri



Jeffrey M. Reder, P.E. P.E. # PE-2010003345

Montana



Daniel J. Clark, P.E. P.E. # 28452

CRE Project #: 23.534.01



Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com

Nebraska



Daniel J. Clark, P.E. P.E. # E-14098

Nevada



Jeffrey M. Reder, P.E. P.E. # 020117

New Hampshire



Daniel J. Clark, P.E. P.E. # 13605

New Jersey



Jeffrey M. Reder, P.E. P.E. # 24GE05300600

New Mexico



Daniel J. Clark, P.E. P.E. # 20482

New York



It is a violation of law for any person, unless acting under the direction of a licensed professional engineer, to alter this document in any way. If any part of this document is altered, the altering engineer shall affix to this document their seal and the notation "altered by" followed by their signature, the date, and description.

Jeffrey M. Reder, P.E. P.E. # 097763-1

North Carolina



Jeffrey M. Reder, P.E. P.E. # 046939

North Dakota



Daniel J. Clark, P.E. P.E. # PE-6586

Ohio



Jeffrey M. Reder, P.E. P.E. # E-67450

CRE Project #: 23.534.01



Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com





Jeffrey M. Reder, P.E. P.E. # 24780

Oregon



EXPIRES: _12/31/2024_

Jeffrey M. Reder, P.E. P.E. # 93904PE

Pennsylvania



Jeffrey M. Reder, P.E. P.E. # PE77455

Rhode Island



Jeffrey M. Reder, P.E. P.E. # 9610

South Carolina



Jeffrey M. Reder, P.E. P.E. # 35797

South Carolina



Clark Reder Engineering # 4827

South Dakota



Daniel J. Clark, P.E. P.E. # 10989

Tennessee



Jeffrey M. Reder, P.E. P.E. # 00113846

Texas



Jeffrey M. Reder, P.E. P.E. # 124100


CRE Project #: 23.534.01



Phone: (513) 851-1223 Fax: (513) 297-0934 www.clarkreder.com

Virginia Utah Vermont lo. 7536302-220 Lic. No. 402061022 03/07/20 Jeffrey M. Reder, P.E. Jeffrey M. Reder, P.E. Daniel J. Clark, P.E. P.E. # 7536302-2203 P.E. # 018.0072612 P.E. # 402061022 Washington **West Virginia** Wisconsin Jeffrey M. Reder, P.E. Jeffrey M. Reder, P.E. Daniel J. Clark, P.E. P.E. # 56469 P.E. # 18628 P.E. # E-41230 **Wyoming** Jeffrey M. Reder, P.E. P.E. # 13434

CRE Project #: 23.534.01





- INDICATES NO BALLAST FOR AN OPEN STRUCTURE (NO SCRIM OR RIGGING) @ 40 MPH (64 km/hr), SCRIM INSTALLED ON BACK DROP, ROOF 1 SIDEWALL AND BANNER KIT SCRIMS @ 15 MPH (24 km/hr) OR SCRIM INSTALLED ON BACKDROP AND ROOF 1 SIDEWALL ONLY @ 20 MPH (32 km/hr).

INDICATES 500# (230 Kg) BALLAST FOR AN OPEN STRUCTURE (NO SCRIM OR RIGGING) @ 45 MPH (72 km/hr), SCRIM INSTALLED ON BACKDROP, ROOF 1 SIDEWALL AND BANNER KIT SCRIMS @ 15 MPH (24 km/hr) OR SCRIM INSTALLED ON BACKDROP AND ROOF 1 SIDEWALL ONLY @ 20 MPH (32 km/hr).

- INDICATES 2,000# (910 Kg) BALLAST FOR AN OPEN STRUCTURE (NO SCRIM OR RIGGING) @ 45 MPH (72 km/hr), SCRIM INSTALLED ON BACKDROP, ROOF 1 SIDEWALL AND BANNER KIT SCRIMS @ 15 MPH (24 km/hr) OR SCRIM INSTALLED ON BACKDROP AND ROOF 1 SIDEWALL ONLY @ 30 MPH (48 km/hr).

NOTE: SEE HIGH WIND ACTION PLAN THIS SHEET.





GENERAL STRUCTURAL NOTES

CODES AND REFERENCE

- 2015 INTERNATIONAL BUILDING CODE
- ASCE 7-10 MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES
- ASCE 37-14 DESIGN LOADS ON STRUCTURES UNDER CONSTRUCTION
- 4. ANSI E1.21-2013 ENTERTAINMENT TECHNOLOGY, "TEMPORARY GROUND-SUPPORTED OVERHEAD STRUCTURES USED TO COVER THE STAGE AREAS AND SUPPORT EQUIPMENT IN THE PRODUCTION OF OUTDOOR ENTERTAINMENT EVENTS"
- 5. ANSI E1.2-2006 ENTERTAINMENT TECHNOLOGY, "DESIGN, MANUFACTURE AND USE OF ALUMINUM TRUSSES AND TOWERS"
- 6. ALUMINUM DESIGN MANUAL, 2015 EDITION

<u>DESIGN LOADS</u>

1. DEAD LOAD: SELFWEIGHT OF STRUCTURE

AISC STEEL MANUAL, 14TH EDITION

- ROOF RIGGING LOADS:
- A. SEE BEAM LOADING CHART ON SHEET S1.2
- NOTE: ROOF IS A SUN SHADE SYSTEM ONLY. IT HAS NOT BEEN DESIGNED FOR PERSONNEL ACCESS OR TO SUPPORT RAIN OR SNOW LOADS.
- STAGE DECK LOADS:
- A. LIVE LOAD: 50 PSF
- WIND LOAD:**
- A. DESIGN WIND SPEED: 45 MPH (BARE STRUCTURE NO SCRIMS ATTACHED)
- B. DESIGN WIND SPEED :30 MPH (WITH ONLY BACKDROP, ROOF 1 SIDEWALL SCRIM, AND FRONT SKIRT SCRIM ATTACHED)
- C. DESIGN WIND SPEED: 15 MPH (WITH BACKDROP, ROOF 1 SIDEWALL SCRIM, FRONT SKIRT AND BANNER KIT SCRIMS*** ATTACHED) D. EXPOSURE C
- E. IMPORTANCE FACTOR: 1.0
- 5. SEISMIC LOADS DO NOT CONTROL THE DESIGN OF THIS STRUCTURE.
- SEE UPLIFT BALLAST PLAN THIS SHEET FOR REQUIRED BALLAST *** BANNER KIT CONSISTS OF (X1) UPPER CENTER CROSS BANNER, (X1) LEFT AND (X1) RIGHT SIDE BANNER (3 SCRIMS TOTAL)

CONSTRUCTION AND SAFETY

- 1. ENGINEER SHALL NOT BE RESPONSIBLE FOR MEANS, METHODS, OR SEQUENCE OF CONSTRUCTION UNLESS SPECIFICALLY STATED ON THE DRAWINGS.
- ENGINEER HAS DESIGNED THE STRUCTURES FOR THEIR FINAL AS-BUILT CONDITION. ENGINEER IS NOT RESPONSIBLE FOR TEMPORARY STABILITY OF STRUCTURES DURING ERECTION UNLESS SPECIFICALLY STATED ON THE DRAWINGS.
- 3. STRUCTURE HAS BEEN DESIGNED AS A TEMPORARY STRUCTURE THAT SHALL BE IN PLACE FOR LESS THAN 6 WEEKS.

STRUCTURAL STEEL

- 1. STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING UNLESS NOTED OTHERWISE ON THE DRAWINGS:
- A. ROLLED WIDE FLANGE SHAPES: ASTM A992, FY = 50 KSI
- B. MISC PLATE, BAR, ANGLES AND CHANNELS: ASTM A36, FY = 36 KSI
- C. PIPE SHAPES: ASTM A53, TYPE E OR S, GRADE B, FY = 35 KSI
- D. HSS RECTANGULAR TUBE: ASTM A500 GR B, FY = 46 KSI E. HSS ROUND TUBE: ASTM A500 GR B, FY = 42KSI
- F. BOLTS OR SCAFFOLD CONNECTION PINS: SAE J429 GRADE 5 BOLTS (FY=92 KSI) UNLESS NOTED OTHERWISE
- WELDING SHALL BE IN ACCORDANCE WITH THE AMERICAN WELDING SOCIETY LATEST EDITION.
- 3. FIELD CONNECTIONS SHALL BE BOLTED OR CONNECTED WITH APPROVED SCAFFOLD CONNECTORS.

- 1. ALUMINUM SHALL CONFORM TO THE FOLLOWING UNLESS NOTED OTHERWISE ON THE DRAWINGS:
- A. MEMBER ALLOY: 6061-T6 UNLESS NOTED OTHERWISE
- B. MEMBER ALLOY FOR STAGE ROOF BEAM EXTRUSIONS; 6063-T5
- C. MEMBER ALLOY FOR STAGE DECK EXTRUSIONS; 6063-T6
- D. WELD FILLER ALLOW: 4043 (MIN)
- 2. ALL DETAILING, FABRICATION AND ERECTION SHALL CONFORM TO THE ALUMINUM ASSOCIATION ALUMINUM DESIGN MANUAL, 2010 EDITION. WELDING SHALL BE IN ACCORDANCE WITH THE AMERICAN WELDING SOCIETY LATEST EDITION.
- 4. FIELD CONNECTIONS SHALL BE BOLTED UNLESS SPECIFIED OTHERWISE ON THE DRAWINGS.

WIRE ROPE AND RIGGING ACCESSORIES

- 1. WIRE ROPE 3/8" OR LESS IN DIAMETER: 7X19 GAC, MEETING FEDERAL SPEC. RR-W-410E
- 2. WIRE ROPE 7/16" OR GREATER IN DIAMETER: 6X19 IWRC, MEETING FEDERAL SPEC. RR-W-410D, TYPE 1 CLASS 2
- 3. SHACKLES: GALVANIZED, SCREW PIN ANCHOR TYPE, ASTM A153 4. TURNBUCKLES: GALVANIZED, ASTM F-1145
- 5. FORGED WIRE ROPE CLIPS: GALVANIZED, MEETING FEDERAL SPEC. FF-C-450 TYPE I CLASS I
- 6. WIRE ROPE THIMBLES: GALVANIZED, MEETING FEDERAL SPEC. FF-T-276B TYPE II
- WIRE ROPE THIMBLES: GALVANIZED, MEETING FEDERAL SPEC. FF-T-276B TYPE II
- RATCHET STRAPS:
- a. RATCHET STRAPS SHALL BE INSTALLED PER THE MANUFACTURER'S WRITTEN INSTRUCTIONS TO DEVELOP THE RATED WORKING LOAD OF THE STRAP.
- b. RATCHET STRAPS WITH OPEN ENDED HOOKED CONNECTION SHALL HAVE A POSITIVE CONNECTION TO THE ATTACHMENT POINT. EXAMPLE: USE A 5/8" SHACKLE BETWEEN THE BARS

1. PER CLIENTS REQUEST, THE FOUNDATION DESIGN AND GENERAL FOUNDATION NOTES BASED ON THE ASSUMPTION OF FAVORABLE SOIL CONDITIONS. ALL FOUNDATION ASSEMBLIES SHALL BEAR ON LEVEL (WITHIN 1 IN 12) GROUND

ROOF HOISTING

- 1. ALL BALLAST SHALL BE IN PLACE PRIOR TO HOISTING ROOF SYSTEM.
- 2. ROOF SYSTEM SHALL NOT BE HOISTED IN WIND SPEEDS GREATER THAN 10 MPH.

- 1. BRIDLES SHALL NOT BE USED UNLESS SPECIFICALLY NOTED BY THE ENGINEER OF RECORD.
- 2. DO NOT EXCEED THE ALLOWABLE RIGGING LOADS SHOWN ON SHEET S1.2 WITHOUT THE WRITTEN APPROVAL OF THE ENGINEER OF RECORD.

INSPECTIONS

1. ALL TRUSS UNITS, SCAFFOLD AND/OR OTHER RIGGING EQUIPMENT SHALL BE VISUALLY INSPECTED PRIOR TO ERECTION. DAMAGED OR CORRODED EQUIPMENT SHALL NOT BE USED. FIELD MODIFICATIONS SHALL BE APPROVED BY THE ENGINEER OF RECORD PRIOR TO INSTALLATION.

OPERATIONS MANAGEMENT PLAN

IMPLEMENTATION OF PLAN

- 1. PRIOR TO EACH INSTALLATION, THE <u>VENUE/STAGE</u> <u>OWNER</u> SHALL DESIGNATE A RESPONSIBLE PERSON IN CHARGE OF IMPLEMENTING ALL PHASES OF THE
- 2. A MEETING SHALL BE HELD AT THE VENUE WITH THE PROMOTER, OWNER OR STAGE MANAGER TO DISCUSS THE HIGH WIND ACTION PLAN AND OTHER OPERATIONAL
- 3. THE METHOD OF INITIATING EVENT CANCELLATION MUST BE OUTLINED EXPLICITLY PRIOR TO THE EVENT ALLOWING FOR IMMEDIATE ACTION IF NECESSARY. 4. A COPY OF THIS PLAN SHOULD BE PROVIDED TO LOCAL POLICE OR FIRE DEPARTMENTS IN ORDER TO HELP USHER PATRONS IN THE EVENT OF AN EVACUATION.

HIGH WIND ACTION PLAN WITH NO BALLAST INSTALLED

- 1. THE HIGH WIND ACTION PLAN SHALL BE IN EFFECT FOR THE ENTIRETY OF THE EVENT. AN EVENT SHALL BE DEFINED AS STARTING AT THE INITIAL COMMENCEMENT OF THE STRUCTURE INSTALLATION AND ENDING ONCE THE STRUCTURE IS COMPLETELY DISMANTLED.
- 2. A COMPETENT RESPONSIBLE PERSON FROM THE VENUE OR RIGGING COMPANY SHALL BE PRESENT FOR THE DURATION OF THE EVENT (SEE ABOVE) TO IMPLEMENT THE HIGH WIND ACTION PLAN.
- 3. A REGULAR LIAISON WITH LOCAL AIRPORTS AND/OR WEATHER INFORMATION CENTERS SHALL BE MAINTAINED TO ASCERTAIN IF ANY SIGNIFICANT WEATHER EVENTS ARE EXPECTED IN THE IMMEDIATE VICINITY OF THE STRUCTURE
- 4. AN ANEMOMETER SHALL BE PLACED ON THE STRUCTURE TO MONITOR WIND SPEEDS. THE ANEMOMETER SHALL BE PLACED AT THE TOP OF A TOWER OR AN ADJACENT STRUCTURE AT A HEIGHT EQUIVALENT TO THE HEIGHT OF THE TOWER. THE ANEMOMETER SHALL BE LOCATED WITHIN 50 YARDS OF THE STRUCTURE.
- 5. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 15 MPH (24 km/hr): ALL SCRIM ASSOCIATED WITH THE BANNER PACKAGE SHALL BE REMOVED FROM THE SYSTEM. THIS INCLUDES THE BANNER SCRIM ON TOP OF THE STAGE THAT CONCEALS THE SPEAKER WING WIRES AND THE SPEAKER WING BANNER SCRIM. LOWERING OF SCRIM SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- 6. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 20 MPH (32 km/hr): ALL SCRIM SHALL BE REMOVED FROM THE SYSTEM. ALL RIGGING EQUIPMENT AND SPEAKER CLUSTERS SHALL BE LOWERED TO THE GROUND AND SECURED. LOWERING OF SCRIM OR EQUIPMENT SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- 7. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 40 MPH (64 km/hr): ALL SHOW OPERATIONS SHALL CEASE AND THE IMMEDIATE AREA SHALL BE EVACUATED. LOWER ROOF IF TIME PERMITS AND WIND SPEEDS ARE BELOW 15 MPH. ALL PERSONNEL SHOULD MAINTAIN SAFE DISTANCE FROM THE ROOF SYSTEM AS COLLAPSE MAY
- 8. THE HIGH WIND ACTION PLAN SHALL BE POSTED AT A CONSPICUOUS AREA ON SITE. IT MUST BE AVAILABLE AT ALL TIMES TO VENUE OPERATORS AND CREW.

HIGH WIND ACTION PLAN WITH 500# (230 kg) BALLAST INSTALLED @ 4 LOCATIONS

- 1. THE HIGH WIND ACTION PLAN SHALL BE IN EFFECT FOR THE ENTIRETY OF THE EVENT. AN EVENT SHALL BE DEFINED AS STARTING AT THE INITIAL COMMENCEMENT OF THE STRUCTURE INSTALLATION AND ENDING ONCE THE STRUCTURE IS COMPLETELY DISMANTLED.
- 2. A COMPETENT RESPONSIBLE PERSON FROM THE VENUE OR RIGGING COMPANY SHALL BE PRESENT FOR THE DURATION OF THE EVENT (SEE ABOVE) TO IMPLEMENT THE HIGH WIND ACTION PLAN.
- 3. A REGULAR LIAISON WITH LOCAL AIRPORTS AND/OR WEATHER INFORMATION CENTERS SHALL BE MAINTAINED TO ASCERTAIN IF ANY SIGNIFICANT WEATHER EVENTS
- ARE EXPECTED IN THE IMMEDIATE VICINITY OF THE STRUCTURE 4. AN ANEMOMETER SHALL BE PLACED ON THE STRUCTURE TO MONITOR WIND SPEEDS. THE ANEMOMETER SHALL BE PLACED AT THE TOP OF A TOWER OR AN
- ADJACENT STRUCTURE AT A HEIGHT EQUIVALENT TO THE HEIGHT OF THE TOWER. THE ANEMOMETER SHALL BE LOCATED WITHIN 50 YARDS OF THE STRUCTURE. 5. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 15 MPH (24 km/hr): ALL SCRIM ASSOCIATED WITH THE BANNER PACKAGE SHALL BE REMOVED FROM THE SYSTEM. THIS INCLUDES THE BANNER SCRIM ON TOP OF THE STAGE THAT CONCEALS THE SPEAKER WING WIRES AND THE SPEAKER WING BANNER SCRIM. LOWERING OF SCRIM SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- 6. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 20 MPH (32 km/hr): ALL SCRIM SHALL BE REMOVED FROM THE SYSTEM. ALL RIGGING EQUIPMENT AND SPEAKER CLUSTERS SHALL BE LOWERED TO THE GROUND AND SECURED. LOWERING OF SCRIM OR EQUIPMENT SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- 7. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 45 MPH (72 km/hr): ALL SHOW OPERATIONS SHALL CEASE AND THE IMMEDIATE AREA SHALL BE EVACUATED. LOWER ROOF IF TIME PERMITS AND WIND SPEEDS ARE BELOW 15 MPH. ALL PERSONNEL SHOULD MAINTAIN SAFE DISTANCE FROM THE ROOF SYSTEM AS COLLAPSE MAY
- 8. THE HIGH WIND ACTION PLAN SHALL BE POSTED AT A CONSPICUOUS AREA ON SITE. IT MUST BE AVAILABLE AT ALL TIMES TO VENUE OPERATORS AND CREW.

HIGH WIND ACTION PLAN WITH 2000# (910 kg) BALLAST INSTALLED @ 4 LOCATIONS

- 1. THE HIGH WIND ACTION PLAN SHALL BE IN EFFECT FOR THE ENTIRETY OF THE EVENT. AN EVENT SHALL BE DEFINED AS STARTING AT THE INITIAL COMMENCEMENT OF THE STRUCTURE INSTALLATION AND ENDING ONCE THE STRUCTURE IS COMPLETELY DISMANTLED.
- 2. A COMPETENT RESPONSIBLE PERSON FROM THE VENUE OR RIGGING COMPANY SHALL BE PRESENT FOR THE DURATION OF THE EVENT (SEE ABOVE) TO IMPLEMENT
- 3. A REGULAR LIAISON WITH LOCAL AIRPORTS AND/OR WEATHER INFORMATION CENTERS SHALL BE MAINTAINED TO ASCERTAIN IF ANY SIGNIFICANT WEATHER EVENTS
- ARE EXPECTED IN THE IMMEDIATE VICINITY OF THE STRUCTURE 4. AN ANEMOMETER SHALL BE PLACED ON THE STRUCTURE TO MONITOR WIND SPEEDS. THE ANEMOMETER SHALL BE PLACED AT THE TOP OF A TOWER OR AN
- ADJACENT STRUCTURE AT A HEIGHT EQUIVALENT TO THE HEIGHT OF THE TOWER. THE ANEMOMETER SHALL BE LOCATED WITHIN 50 YARDS OF THE STRUCTURE. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 15 MPH (24 km/hr): ALL SCRIM ASSOCIATED WITH THE BANNER PACKAGE SHALL BE REMOVED FROM THE SYSTEM. THIS INCLUDES THE BANNER SCRIM ON TOP OF THE STAGE THAT CONCEALS THE SPEAKER WING WIRES AND THE SPEAKER WING BANNER SCRIM. LOWERING OF SCRIM SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 30 MPH (48 km/hr): ALL SCRIM SHALL BE REMOVED FROM THE SYSTEM. ALL RIGGING EQUIPME CLUSTERS SHALL BE LOWERED TO THE GROUND AND SECURED. LOWERING OF SCRIM OR EQUIPMENT SHALL BE DONE FROM THE GROUND BY MEANS OF REMOTELY ACTIVATED EQUIPMENT SUCH AS MOTORS OR MECHANICAL RELEASES.
- 7. WHEN WIND SPEEDS ARE EXPECTED TO EXCEED 45 MPH (72 km/hr): ALL SHOW OPERATIONS SHALL CEASE AND THE IMMEDIATE AREA SHALL BE EVACUATED. LOWER ROOF IF TIME PERMITS AND WIND SPEEDS ARE BELOW 15 MPH. ALL PERSONNEL SHOULD MAINTAIN SAFE DISTANCE FROM THE ROOF SYSTEM AS COLLAPSE MAY
- 8. THE HIGH WIND ACTION PLAN SHALL BE POSTED AT A CONSPICUOUS AREA ON SITE. IT MUST BE AVAILABLE AT ALL TIMES TO VENUE OPERATORS AND CREW.

SNOW/RAIN REMOVAL

1. THE ROOF SKIN HAS NOT BEEN DESIGNED TO SUPPORTED PONDED WATER OR SNOW. REMOVE ANY AND ALL SUCH ACCUMULATIONS.



10091 Mosteller Lane West Chester, OH 45069 513 851 1223



THIS DOCUMENT IS THE PRODUCT AND EXCLUSIVE PROPERTY OF CLARK-REDER ENGINEERING, INC. NEITHER THE DOCUMENT NOR THE INFORMATION IT CONTAINS MAY BE COPIED OR USED FOR OTHER THAN THE SPECIFIC PURPOSE FOR WHICH IT WAS PREPARED, WITHOUT THE WRITTEN CONSENT OF CLARK REDER ENGINEERING, IN



PROGRESSIVE | PITTSBURG, !

STAG


MOBILE

2X24

ISSUE/REVISIONS REVISION DESCRIPTION - DATE

TE: 1/8/2018 RE PROJECT NO: 17.534.03

> WN RV: AAW/DDL BALLAST PLAN



BEAM LOADING CHART WITHOUT PRT CANTILEVER					
BEAM CALLOUT	UNIFORMLY DISTRIBUTED LOAD	CENTER POINT LOAD	THIRD POINT LOAD	QUARTER POINT LOAD	
BEAM CALLOUT		<u> </u>	Ţ Ţ	Ţ ţ ţ	
I-BEAM #1	25 lb/ft	400 lb	300 lb	200 lb	
I-BEAM #2	57 plf	-	-	-	
I-BEAM #3	50 lb/ft	800 lb	500 lb	330 lb	
SPEAKER BEAM		2,000 lb			

ROOF FRAMING PLAN

1/2" = 1'-0"

NOTE:

1. REFERENCE EL = GRADE = 100'-0"

2. FLOOR EL 103'-9"±

- SEE SHEET S5.1 FOR GENERAL NOTES, HIGH WIND ACTION PLAN, AND BALLAST REQUIREMENTS
 SCRIM ON SIDES OF STRUCTURE MUST BE INSTALLED WITH A 3 FOOT SAG AT MIDSPAN TO PREVENT EXCESSIVE LATERAL LOADS ON THE STRUCTURAL
- **MEMBERS** 5. FRAMING MEMBERS ARE ALUMINUM UNLESS OTHERWISE NOTED
- 6. PRT CANTILEVER OPTION IN DETAIL 10/S3.1 IS SHOWN ON ONE SIDE OF THE ROOF FRAMING PLAN FOR CLARITY. THE PRT CANTILEVER OPTION IS APPLICABLE ON BOTH SIDES OF THE ROOF FRAMING PLAN

7.	RIGGING FOR PRT CANTILEVER SHALL BE A VERTICAL DEAD HANG ONLY.
	NO BRIDLE OR LATERAL COMPONENT OF LINE LOAD IS PERMITTED

BEAM LOADING CHART WITH PRT CANTILEVER						
BEAM CALLOUT	UNIFORMLY DISTRIBUTED LOAD	CENTER POINT LOAD	THIRD POINT LOAD	QUARTER POINT LOAD		
BLAM CALLOUT		<u> </u>	Ţ Ţ	Ţ ţ ţ		
I-BEAM #1	25 lb/ft	400 lb	300 lb	200 lb		
I-BEAM #2	57 plf	-	-			
I-BEAM #3	40 lb/ft	610 lb	450 lb	309 lb		
SPEAKER BEAM	BEAM 2,000 lb					





١	
	COPYRIGHT © 2017
Ì	THIS DOCUMENT IS THE PRODUCT AND EXCLUSIVE PROPERTY OF CLARK-REDER ENGINEERING, INC. NEITHER THE DOCUMENT NOR THE INFORMATION IT CONTAINS MAY BE COPIED OR USED FOR OTHER
	THAN THE SPECIFIC PURPOSE FOR WHICH IT WAS PREPARED, WITHOUT THE WRITTEN CONSENT OF CLARK REDER ENGINEERING, INC


ACCOUNT OF THE PARTY OF THE PAR	No.
ROGRESSIVE	A MINI
PRODUCTS INC.	ALEA

STAGE 32X24 MOBILE PROGRESSIVE F PITTSBURG, F

	ISSUE/RE	EVISIONS
Δ	REVISION DESC	CRIPTION - DATE
(8)		

ATE: 1/8/2018 CRE PROJECT NO: 17.534.03 WN BY: AAW/DDL

> ROOF FRAMING PLAN



NOTE:

1. REFERENCE EL = GRADE = 100'-0"

- 2. FLOOR EL 103'-9"± 3. SEE SHEET S5.1 FOR GENERAL NOTES, HIGH WIND ACTION PLAN, AND
- BALLAST REQUIREMENTS.
- 4. SCRIM ON SIDES OF STRUCTURE MUST BE INSTALLED WITH A 3 FOOT SAG AT MIDSPAN TO PREVENT EXCESSIVE LATERAL LOADS ON THE STRUCTURAL

5. FRAMING MEMBERS ARE ALUMINUM UNLESS OTHERWISE NOTED.



١	
	COPYRIGHT © 2017
	THIS DOCUMENT IS THE PRODUCT AND EXCLUSIVE PROPERTY OF CLARK-REDER ENGINEERING, INC. NEITHER THE DOCUMENT NOR THE INFORMATION IT CONTAINS MAY BE COPIED OR USED FOR OTHER
	THAN THE SPECIFIC PURPOSE FOR WHICH IT WAS PREPARED, WITHOUT THE WRITTEN CONSENT OF CLARK REDER ENGINEERING, INC

		V
	DROGRESSIVE	4
8	PRODUCTS INC.	AT

STAGE PROGRESSIVE PRODUCTS PITTSBURG, KS 66762 32X24 MOBILE

ISSUE/REVISIONS
REVISION DESCRIPTION - DATE


WY			
} —			
W			******


DATE: 1/8/2018 CRE PROJECT NO: 17.534.03 AWN BY: AAW/DDL


> PLATFORM FRAMING PLAN

APEX 2016/2420/3224 Mobile Stage










UPDATED RAILS FOR THE 6 STEP VERSION OF THE MOBILE STAGE WHEN PUBLIC ACCESS IS REQUIRED



UPDATED RAILS FOR THE 8STEP VERSION OF THE MOBILE STAGE WHEN PUBLIC ACCESS IS REQUIRED



8 STEP HAND RAILS ARE 104" IN LENGTH WITH INSIDE SPACING AT 4" APART

NOTES:

- DRAWING IS MEANT TO SERVE AS GENERAL DIMENSIONAL REFERNECE ONLY. INFORMATION CONTAINED IS SUBJECT TO CHANGE WITHOUT NOTICE.
- 2. STAIRCASE IS PRIMARILY CONSTRUCTED FROM ALUMINUM, WITH EXCEPTION OF FASTENING CLAMPS AND ALL HARDWARE.
- DIMENSIONS SHOWN ARE REPRESENTATIVE OF STAIRCASE SET UP AT A GIVEN SLOPE THAT CORRESPONDS TO A 40-9/16" STAGE DECK HEIGHT. DIMENSIONS WILL VARY WITH A DIFFERENT STAGE DECK HEIGHT OTHER THAN WHAT IS USTED.
- 4. DETAIL IS THE SAME FOR THE 6 FLIGHT STAIRCASE USED ON THE APEX 2016 & ON THE 8 FLIGHT STAIRCASE USED ON THE APEX 2420, 3224, 4240 & 5040

STAIRCASE GENERAL DIMENSIONS STH - 9/19/17





125 TAYLOR PARKWAY ARCHBOLD, OH 43502

PHONE: (419) 445-8915 FAX: (419) 445-0367

www.biljax.com

Guard Rail / Bracing


Guard Railing Description Guard Rail Panel, Vertical, 2'W x 42"H Guard Rail Panel, Vertical, 4'W x 42"H 32 4' Vertical Guard Rail 2' Vertical Guard Rail

APEX 3224

WING BANNER "C"

4'WIDE
BY 23' TALL
70% BLOWTHRU
MESH
W GROMMETS ON
TOP & BOTTOM
EVERY 2'

RESTRICTION
""No wording
should
appear in lower 5"
due to crowdobst rist ion



40'WIDE

*** Barricades may obstruct the lower 4' across the lower stage as well as attendees